


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

H/J-14

**History of original corner establishment:**

None. Corner established with this survey.



**Description of corner evidence found:**

None.

**Description of monument and accessories established to perpetuate the original location of this corner:**

At position established by proper subdivision of section from survey control...  
Set 3" diam brass rock cap with 3" long stem flush with solid rock slab and secured with concrete mortar. Placed 6' steel fence post alongside with signs 54-2 and 54-9.

**New bearing trees established:**

Ponderosa pine 13" dia brs N44°W, 85.0' dist mkd C S SW 1/64 S 10 BT.  
White fir 13" dia brs S55½°W, 26.7' dist mkd C S SW 1/64 S 10 BT.

No mound made because there was no earth or stone available.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly established by me & witnessed by F.S. Munro on September 24, 1989.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of... County Surveyor..... County of... Union.....  
State of... Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL)

<b>UNION COUNTY SURVEYOR</b>	
(DEPUTY)	
Date Received	<u>3-12-90</u>
Date Filed	<u>3-12-90</u>
By	<u>Gregory T. Blackman</u>
File No.	<u>11-90R</u>

\*GPO-591-971, 1988